

Important Note

All materials in these slides are for the purposes of the conference only and NOT meant for any other purposes. If you wish to use the materials for any other purposes, please seek the consent of the Building and Construction Authority (BCA).

SINGAPORE'S CONSTRUCTION PRODUCTIVITY JOURNEY

Hugh Lim

CEO, Building and Construction Authority (BCA), Singapore

Building and Construction  Authority

We shape a **safe** **high quality** **sustainable** and **friendly** built environment.

SCOPE OF PRESENTATION

- i** Singapore's Construction Productivity Journey
- ii** Design for Manufacturing and Assembly (DfMA)
- iii** Integrated Digital Delivery (IDD)
- iv** The Way Forward

Singapore's Construction Industry is Transforming

Key Trends driving our transformation



Greater **Urbanisation** and Increasing **Manpower Squeeze**

- Need to adopt more **advanced construction technologies** (e.g. DfMA)



Gearing towards **Digital Revolution**


- **Integrated Digital Delivery (IDD)** as key enabler of DfMA adoption



Dealing with **Climate Change**

- Greater focus on **sustainable construction practices**

Singapore's Construction Industry Transformation Map (ITM)





Design for

Manufacturing
(off-site and automation)

and **A**ssembly
(on-site)

Moving work offsite will improve productivity in 3 ways

- **Controlled** factory environment
- Greater scope for **automation**
- Options for **offshoring**

- ✓ Adopting Prefabrication
 - **Modular Design**

DfMA Changes the Way We Build

DfMA

Digital Engineering

Continuum of DfMA technology

Components:
Incremental Improvement...

...Integrated Assemblies:
Game-Changing Improvement

Prefab components

Advanced Prefab Systems

Integrated Sub-assemblies


Fully-integrated Integrated Assemblies

Structural



40%

Architectural




MEP



Key Objectives:

1. *Increase adoption* to improve productivity
2. *Reduce cost premium* for sustained adoption
3. *Sufficient capacity and capabilities* to support adoption



Creating Lead Demand for DfMA

A

DEMAND

Taking the lead - **Public sector** projects adopting DfMA

Prefabricated Prefinished Volumetric Construction

- **16** projects

(4 completed , 12 on-going)



Prefabricated Mechanical, Electrical and Plumbing

- **2** projects

(on-going)

9 upcoming projects



Mass Engineered Timber

- **11** projects

(3 completed , 8 on-going)



Structural Steel

- **11** projects

(2 completed , 9 on-going)

State Courts Towers



Creating Lead Demand for DfMA

A

DEMAND

Public sector taking the lead, in close collaboration with industry

Championing productive technology adoption and processes

DfMA Technology



Integrated BIM



Procurement Methods



Advisory panel of industry experts for DfMA projects



DfMA project implementation



Creating Lead Demand for DfMA

A

DEMAND

Government Land Sale (GLS) Sites

Specifying DfMA technology adoption

Total number of sites to date

PPVC

20 residential GLS sites



Structural Steel

2 commercial GLS sites



Productivity Outcomes

1 residential GLS site

Pilot Concept & Price tender approach

More sites to be launched

Private developments

Voluntary DfMA technology adoption

PPVC hotel



Crowne Plaza Extension

PPVC residential



Brownstone

MET



Singapore Sustainability Academy

Funding support for voluntary DfMA adoption by private sector

Note:

PPVC – Prefabricated and Pre-finished Volumetric Construction

MET – Mass Engineered Timber

Accredited suppliers listed on BCA's website

Building Innovation Panel (BIP)

- Ensuring *design* complies with regulatory requirements

PPVC Manufacturer Accreditation Scheme (MAS)

- Ensuring high *quality* in PPVC production

Building and Construction Authority 


SINGAPORE

 PUB
Water for All: Conserve, Value, Enjoy

Land Transport Authority 

 HOUSING &
DEVELOPMENT
BOARD

 MINISTRY OF
MANPOWER

 National
Environment
Agency
Safeguard • Nurture • Cherish

 jtc
Breaking New Ground

 URBAN
REDEVELOPMENT
AUTHORITY

 SCDF
The Life Saving Force

Suppliers Capabilities Established

B

SUPPLY

Highly automated facilities for production, quality ensured

- ✓ Multi-storey prefabrication hubs with automation and mechanization
- ✓ Improved quality control in factory production
- ✓ Considerably reduce labour usage on-site for higher productivity

More will complete in the next 3 years



Courtesy of: GREYFORM



Automated Steel Reinforcement Fabrication



Courtesy of: GREYFORM



Automated Pallet Circulation Plant



Teambuild



Soilbuild

Competent Suppliers

DfMA

Digital
Engineering


24 SUPPLIERS (*Through Building
Innovation Panel*)

Steel PPVC

- 5) AM Modular
- 6) CIMC
- 7) Tiong Seng
- 8) Dragages
- 9) Mod Prefab
- 10) TTJ
- 11) Quicksmart
- 12) Kong Hwee
- 13) Imax
- 14) TK Modular Construction
- 15) Lightrus

Concrete PPVC

- 16) SPP System
- 17) Excel Precast
- 18) Vico
- 19) Dragages
- 20) Mod Prefab
- 21) Prefab Tech
- 22) CS Corp
- 23) Qingjian
- 24) China



PPVC – Most Promising DfMA Technology

DfMA

Digital Engineering

PPVC yields significant productivity improvement

Components:
Incremental Improvement...

...Integrated Assemblies:
Game-Changing Improvement

Prefab components

Advanced Prefab Systems

Integrated Sub-assemblies

Fully-integrated Integrated Assemblies

Structural



Architectural



MEP



What is PPVC?

1. Modules manufactured, fitted out in Factory



Courtesy of: Moderna Homes

2. Transport to site



Courtesy of: Teambuild

3. Easy Installation on-site



Courtesy of: OUE

Completed PPVC Unit

DfMA

Digital
Engineering

No different from conventional construction, but better quality finishes



Courtesy of: Teambuild

Living Room



Courtesy of: Teambuild

Kitchen View From Living




Courtesy of: Teambuild

Kitchen




Courtesy of: Teambuild

Common Area Within Unit



Courtesy of: Teambuild


Bedroom



Courtesy of: Teambuild

Bathroom

Types of PPVC




Courtesy of: ADDP

1

REINFORCED CONCRETE PPVC MODULE

Wall: Concrete
Floor: Concrete



Courtesy of: ADDP

2

STEEL PPVC MODULE

Wall: Steel frame with lightweight walls
Floor: Concrete or Lightweight Flooring System

Singapore PPVC Projects

DfMA

Digital
Engineering

Wide range of project types done in PPVC

PPVC

- **31** projects
(6 completed , 25 on-going)

Development types:
Hostel, Nursing Home,
Hotel, Dormitory and
Residential

Residential

COMPLETED



Photo: CDL

10-Storey Brownstone
Executive Condo

ON-GOING



Photo: Moderna

12-Storey Wisteria
Commercial & Condo

ON-GOING



Photo: EL Development

36-Storey Parc Riviera
Condo

ON-GOING



Photo: UOL

40-Storey
Clement Canopy Condo

Hostel

COMPLETED



Photo: NTU

13-Storey
NTU Hostel

Dormitory

COMPLETED



Photo: JTC

9-Storey Dormitory
JTC Space @ Tuas

Nursing Home

COMPLETED



Photo: MOHH

9-Storey Woodlands
Nursing Home

Hotel

COMPLETED



Photo: OUE

10-Storey Crowne Plaza
Hotel Extension

Teambuild - A PPVC Pioneer in Singapore

West Terra, Public Housing



Courtesy of: HDB

15% manpower savings

2013 2014

The Brownstone, Executive Condo



Courtesy of: CDL

20% manpower savings

2015 2016

Valley spring, Public Housing



Courtesy of: HDB

Construction in progress

2017

Parc Riviera, 36 storey condo



Courtesy of: EL Development

Construction in progress

2018



Gen 1

Courtesy of: Teambuild

Minimal finishes, incomplete modules, with extensive wet joints



Gen 2

Courtesy of: Teambuild

Greater modularization with less wet joints, but still minimal finishes and no floor slab



Gen 3

Courtesy of: Teambuild

Complete 6-sided, **fully prefinished** modules

Crowne Plaza Airport Hotel Extension

- Made possible by a strong project team, comprising architect, engineer, contractor and fabricator



One of Singapore's pioneer PPVC projects

Developer:
OUE Airport Hotel Pte Ltd

Architect:
WOHA Architects Pte Ltd

Structural Engineer:
RSP Architects & Planners Pte Ltd

M&E Engineer:
Surbana International Consultants Pte Ltd

Main Contractor:
Dragages Singapore Pte Ltd

PPVC Supplier:
Unitised Building Consulting (Aust) Pty

6 months time savings, 44% manpower savings

STEEL
PPVC

- PPVC for high-rise developments

Clement Canopy Condominium

Construction ongoing



Courtesy of: UOL

CONCRETE PPVC

40-storey condominium
(World's tallest concrete PPVC building)

Developer:
Singland Homes & UOL Venture Investments

Architect:
ADDP Architects LLP

Structural Engineer:
Tham & Wong LLP

M&E Engineer:
J Roger Preston (S) Pte Ltd

Main Contractor:
Dragages Singapore Pte Ltd

PPVC Supplier:
Dragages Singapore Pte Ltd

Industry Capabilities developed in PPVC

Clement Canopy Condominium

Onsite Assembly

Modularisation



Offsite fabrication



Courtesy of: Dragages



Courtesy of: Dragages



Courtesy of: Dragages

Designing open-concept PPVC systems

Consultants design capabilities made open-concept PPVC design possible

Woodlands Nursing Home

3 months time savings,
24% manpower savings



Developer:
MOH Holdings Pte Ltd (MOHH)
Architect, Structural Engineer, M&E:
Surbana International Consultants
Main Contractor:
Dragages Singapore Pte Ltd
PPVC Supplier:
Dragages Singapore Pte Ltd

STEEL
PPVC

Courtesy of: MOHH

JTC Space @ Tuas

16%
manpower savings



Developer:
JTC Corporation
Architect:
SAA Architects Pte Ltd
Structural Engineer:
Aecom Singapore Pte Ltd
Main Contractor:
Tiong Seng Contractors Pte Ltd
PPVC Supplier:
Tiong Seng Contractors Pte Ltd


STEEL
PPVC

Courtesy of: JTC

Open concept PPVC systems

Woodlands Nursing Home


Modular system for various bedroom functions



Typical Bedroom

Courtesy of: Dragages

JTC Space @ Tuas (Dormitory)



Modular Layout

Courtesy of: Tiong Seng

PPVC projects achieving variety of building forms

Singapore PPVC Projects

- With capable architects on board, creative building features can be achieved

Overseas PPVC Projects

Habitat 67, Canada (Residential)

By Arch Moshe Safdie



Courtesy of: Habitat 67

12 STOREYS

Victoria Hall, London



Courtesy of: Victoria Hall

19 STOREYS

Crowne Plaza Hotel Extension



Courtesy of: OUE

10 STOREYS

Wisteria Condominium



Courtesy of: Moderna Homes

Mixed residential and commercial

12 STOREYS

Prefab Mechanical, Electrical and Plumbing (MEP) Systems

Components:
Incremental Improvement...

...Integrated Assemblies:
Game-Changing Improvement



Prefab Components



Pre-insulated plastic piping

Sub-assemblies

Include MEP services only



Prefab horizontal services / vertical riser modules

Integrate with architectural/ structural components



Prefab horizontal module with ceiling board



Prefab vertical riser module with catwalk

Integrated Assemblies MEP PPVC

Complete assembly



Prefab plant room

Benefits of Prefab MEP Systems


Better Health and Safety

Neat and tidy factory



Photograph courtesy by DSG Modular, Newcastle, England, UK

Upfront detailed design



Improved Quality and Productivity

Working in a factory environment and at ground level improve productivity



Photograph courtesy by Crown House Manufacturing

Easy to install (lifting one subassembly instead of multiple ducts, pipes, etc.)



Case Study - Global Switch Data Centre

Up to 70% productivity improvement



Courtesy of: Global Switch

Developer:

Global Switch Singapore

Architect:

AWP

M&E Engineer:

Aurecon

Main Contractor:

Gammon

MEP Module Supplier:

Gammon

Project Period:

October 2017 – November 2018

Adopted Prefab MEP Systems

- Horizontal module
- Roof cooling tower modules
- Riser modules
- Plant room modules
- External modules with catwalk


Championing of DfMA is supported by Digital Engineering

Digital Design

Collaborative and coordinated DfMA design using BIM/VDC or other computational tools

Digital Assembly

Using real-time Info-Comm Technology (ICT) to deliver and install on-site



Digital Manufacturing and Fabrication


Integration of BIM/VDC for off-site production through automation, robotics

Note:
IDD – Integrated Digital Delivery


Digital Design - components

DfMA

Digital
Engineering




Digital manufacturing and fabrication - components



Digital Construction and Assembly - components

DfMA

Digital
Engineering




An IDD Scenario

Architect uses BIM to generate design options



Design

Engineers perform analysis



Contractor, Fabricator give early input on constructability



Developer use VR tool to visualise building



Fabricator uses digital DfMA model for production



Supervisor monitors activities in central control room



Manufacturing



Digital data and robotics to drive machinery



DfMA modules delivered just-in-time to site



Digital IDs embedded in DfMA modules



Contractor uses BIM to plan construction



Assembly

Contractor uses BIM-to-Field technology for setting out



PM monitors site using drones



Crane Operator operates smart crane



IDD Platform: Data Storage, Data Exchange, Data Processing, Data Mining, Analytics Engine/Machine Learning

Where to next?

**CHANGING
THE WAY WE BUILD**

DfMA

More projects
to adopt DfMA



From conventional construction..




..to offsite manufacturing




and onsite assembly

IDD


Pilot adoption
of IDD



Digital Design



Digital Manufacturing



Digital Assembly

Developing full suite of digital solutions and capabilities

Collaboration



Industry



Government



Industry

Require close Partnership & Collaboration among Stakeholders

Thank You